



Ludlow, Vermont

A Better Place To Live, Work & Play

REQUEST FOR PROPOSAL

FROM: Village of Ludlow

ATTENTION: Scott Murphy, Municipal Manager

DATE: July 9, 2020

The Village of Ludlow Vermont is seeking BIDS/PROPOSALS from qualified contractors for the following:

GILL TERRACE STORMWATER SYSTEM IMPROVEMENTS

Please see attached specifications and map.

Sealed bids marked “Gill Terrace Stormwater Project” are due in the Municipal Office on Wednesday, July 29, 2020 by 10:00 am. Emailed bids should be sent to Scott Murphy at tmanager@tds.net. Bids will be opened publicly at 10:00 am in the Howard Barton, Jr. Conference Room and may possibly be awarded at the Village Board of Trustees regular meeting on Tuesday, August 4, 2020. Project is to be completed by October 15, 2020.

The Village of Ludlow reserves the right to reject any or all proposals. This solicitation in no way obligates the Village of Ludlow to award a contract.

Certificate of Insurance is required with the bid proposal.

Contractors interested in bidding on the Village Storm Drain Replacement Project should contact Scott Murphy at (802) 228-2841 or Ron Tarbell at (802) 770-9566.

Please submit proposals to:

Village of Ludlow
PO Box 359
Ludlow, VT 05149
Attn: Gill Terrace Stormwater System Improvements

GILL TERRACE STORMWATER SYSTEM IMPROVEMENTS

- Install a 600-foot, 15-inch HDPE storm drain line (pipe supplied by the Village of Ludlow)
- Furnish and install six (6) precast catch basins or Nylo-Plast catch basins
- Trench and pave road with 2.5 X 1.5 asphalt
- Furnish and install new flushing hydrant
- Furnish and install one new precast concrete manhole

Add-On:

- Install 300-foot X 8-inch SDR 35 sewer line (sewer line to be supplied by Village of Ludlow)
- Remove approximately 550-feet of existing asphalt
- Grade, compact and repave new asphalt

Important for Contractors:

Contractor must provide traffic control & proper sign packages.

Contractor must maintain one-lane traffic during the day and two-lane traffic at night.

Project to be completed by October 15, 2020.

- Water
- Sewer
- storm
- Di drop inlet (storm)
- CS curbstop
- ⚡ Firehydrant
- SMH Sewer Manhole

Existing underground

