

REQUEST FOR PROPOSAL

FROM: Town of Ludlow

ATTENTION: Scott Murphy, Municipal Manager

DATE: July 30, 2019

The Town of Ludlow Vermont is seeking BIDS/PROPOSALS from qualified contractors for the following:

SLOPE STABILIZATION PROJECT

The Town of Ludlow is accepting bids to stabilize and re-armor a failing slope on the Okemo Mountain Access Road. Project will include the removal of material, armor bank with type II, IV stone, vegetative growth and to add a steel beam guardrail with galvanized 8' posts.

This project is partially funded through the FY 2020 Better Roads Program and must be completed by June 30, 2020.

Bids marked "Slope Stabilization" are due in the Municipal Office no later than Wednesday, August 21, 2019 at 10:00 am. The bids will be opened and read publicly at 10:00 am in the Town Hall Conference Room. Bid will be awarded at the Select Board's regular meeting in September.

The Town of Ludlow reserves the right to reject any or all proposals. This solicitation in no way obligates the Town of Ludlow to award a contract. A valid Certificate of Insurance showing proof of the contractor's liability and Workers Compensation coverage and naming the Town of Ludlow as an additional insured is required with the bid proposal.

Contractors interested in bidding on the Slope Stabilization Project should contact Ron Tarbell at 802-770-9566.

Please submit proposal by email to tmanager@tds.net or to the following address:

Town of Ludlow
PO Box 359
Ludlow, VT 05149
Attn: Slope Stabilization Project

Town of Ludlow Slope Stabilization Project

Description:

Stabilize and re-armor a failing slope on the Okemo Mountain Access Road. Project will include the removal of material, armor bank with type II, IV stone, vegetative growth and to add a steel beam guardrail with galvanized 8' posts.

Bid shall include, but not limited to, the following:

Item Description	Unit	Quantity (Estimate)
Excavation	CY	400
Granular Borrow	CY	9
Aggregate Shoulders	Ton	5
Stone Fill Type II, Type III & Type IV	CY	280
Galvanized Steel Beam Guardrail with 8' Post	LF	100
Anchor for Steel Beam Rail	Each	2
Flaggers	Hours	80
Mobilization/Demobilization	LS	1
Traffic Control	LS	1
Geotextile Under Stone Fill	SY	150
Seed	LB	50
Fertilizer	LB	40
Agricultural Limestone	Ton	0.2
Straw Mulch	Ton	0.4
Top Soil	CY	40
Temporary Erosion Matting	SY	150

This project is partially funded through the FY 2020 Better Roads Program and must be completed by June 30, 2020.

Road Signs and Traffic Control:

- Complete sign package is required.
- All road signs and traffic control shall be supplied by the contractor.
- Contractor must maintain one-lane traffic during the day.

Contractors interested in bidding on the Slopeside Stabilization Project should contact Ron Tarbell at (highway office) 802-228-2271 or (cell phone) 802-770-9566.