



Ludlow, Vermont

A Better Place To Live, Work & Play

REQUEST FOR BID/ PROPOSAL

FROM: VILLAGE OF LUDLOW
PO BOX 359
LUDLOW, VERMONT 05149

ATTENTION: Scott Murphy, Municipal Manager

DATE: April 8, 2019

The Village of Ludlow is seeking BIDS/PROPOSALS from qualified contractors for Village Sidewalk removal, repair and/or replacement on the following locations. The following area is to be considered:

Pleasant Street (Depot St to Andover St, North side)

- 550' X 5' Concrete Sidewalk
- Town and Outside Vendor to replace/reset curb

High Street

150' x 5' Concrete sidewalk Spot replacement (no curb work)

Add-On (Please submit separate price): Lower Main St (Hammond Hall to Elm St)

350' x 5' Concrete sidewalk (curbing to be reset/replaced by outside vendor)

Please bid:

1. Per /foot cost concrete sidewalk
2. Price should include removal and replacement

General Sidewalk Specifications are attached.

For additional information, please contact Ron Tarbell, Highway Foreman at 802-770-9566. Certificate of appropriate insurance is required with the bid proposal.

➔ Sealed bids marked "2019 Sidewalk Bid" must be received in the Municipal Office by 10:00 am on Monday May 20, 2019 with a bid opening at 10:10 am. (Bids may be emailed to: Tmanager@tds.net.) Bids will be awarded at the Village Board of Trustees regular meeting on June 4, 2019.

Please note: The work is to be started by mid-June and completed by July 31st. The Village of Ludlow reserves the right to reject any or all bids. This solicitation in no way obligates the Village of Ludlow to award a contract.

**VILLAGE OF LUDLOW, VERMONT
CONCRETE SIDEWALKS
GENERAL SPECIFICATIONS**

GENERAL

Furnish all labor, materials, equipment and incidentals required to restore sidewalks.

If the Contractor damages part of a sidewalk which did not need replacing, the entire width of the walk shall be removed and replaced, at the contractor's expense, as specified below. Patch work will not be permitted.

The Contractor shall assume full responsibility for protecting the public against injury due to any phase of the sidewalk construction. Safe and adequate entrance to all businesses and private property shall be maintained by the Contractor, at all times.

PRODUCTS

CEMENT CONCRETE SIDEWALKS AND REINFORCED WIRE MESH:

All materials shall conform to Vermont Standards 618.02. Also, welded wire mesh shall conform to ASTM A 82-A185 which shall meet 7,000 p.s.i.

EXECUTIONS / GENERAL:

Sidewalks shall be constructed in accordance with Vermont Specifications 618.03.

This item shall include all costs for labor, tools, material, equipment and incidentals necessary for the construction of new concrete sidewalks.

CONCRETE SIDEWALKS AND CONCRETE CURBING GENERAL SPECIFICATIONS:

- All sidewalks shall be five (5') feet in width and five (5") inches deep.
- Payment for this item shall be for the actual number of square yards of sidewalk restored at the unit price stated in this proposal.
- The Contractor shall notify the Village of Ludlow 24 hours in advance of pouring concrete.
- The Village of Ludlow shall have the right to inspect preparations for concreting and no concrete shall be placed without prior approval of the Village.
- Must meet State of Vermont Specifications.