



# Ludlow, Vermont

*A Better Place To Live, Work & Play*

## REQUEST FOR BID/ PROPOSAL

FROM: VILLAGE OF LUDLOW  
PO BOX 359  
LUDLOW, VERMONT 05149

ATTENTION: Scott Murphy, Municipal Manager

DATE: March 15, 2022

The Village of Ludlow is seeking BIDS/PROPOSALS from qualified contractors for Village Sidewalk removal, repair and/or replacement on the following locations. The following area is to be considered:

### **Lower High Street (Gleascott Avenue to Main Street)**

- 390' X 5' Concrete Sidewalk
- Remove/Replace 6" of crushed gravel under sidewalk
- Vendor to replace approximately 300 ft. of existing curb with new granite curbing

Please bid on the following:

1. Per /foot cost concrete sidewalk
2. Price should include removal, replacement and cost of curbing

General Sidewalk Specifications are attached.

For additional information, please contact Ron Tarbell, Highway Foreman at 802-770-9566. Certificate of Insurance is required with the bid proposal.

Sealed bids marked "2022 Sidewalk Bid" must be received in the Municipal Office by 10:00 am on Wednesday, April 27, 2022 with a bid opening at 10:00 am. Bids may also be emailed to: [tmanager@tds.net](mailto:tmanager@tds.net). The Sidewalk Project bids will be awarded at the Village Board of Trustees regular meeting on May 3, 2022. Please note: The work is to be completed by July 31, 2022.

**The Village of Ludlow reserves the right to reject any or all bids. This solicitation in no way obligates the Village of Ludlow to award a contract.**

**VILLAGE OF LUDLOW, VERMONT  
FY 2022 CONCRETE SIDEWALKS**

Town & Village of Ludlow, PO Box 359, Ludlow, VT 05149

## **GENERAL SPECIFICATIONS**

### **GENERAL**

Furnish all labor, materials, equipment and incidentals required to restore sidewalks.

Contractor must restore/replace all disturbed areas (i.e. lawns, driveways, roadway, etc.)

Proper/legal sign packages must be in place at the construction site and supplied by each applicant.

If the Contractor damages part of a sidewalk which did not need replacing, the entire width of the walk shall be removed and replaced, at the contractor's expense, as specified below. Patch work will not be permitted.

The Contractor shall assume full responsibility for protecting the public against injury due to any phase of the sidewalk construction. Safe and adequate entrance to all businesses and private property shall be maintained by the Contractor, at all times.

### **PRODUCTS**

#### **CEMENT CONCRETE SIDEWALKS AND REINFORCED WIRE MESH:**

All materials shall conform to Vermont Standards 618.02. Also, welded wire mesh shall conform to ASTM A 82-A185 which shall meet 7,000 p.s.i.

### **EXECUTIONS / GENERAL:**

Sidewalks shall be constructed in accordance with Vermont Specifications 618.03.

This item shall include all costs for labor, tools, material, equipment and incidentals necessary for the construction of new concrete sidewalks.

### **CONCRETE SIDEWALKS AND CONCRETE CURBING GENERAL SPECIFICATIONS:**

- All sidewalks shall be five (5') feet in width and five (5") inches deep.
- Payment for this item shall be for the actual number of square yards of sidewalk restored at the unit price stated in this proposal.
- The Contractor shall notify the Village of Ludlow 24 hours in advance of pouring concrete.
- The Village of Ludlow shall have the right to inspect preparations for concreting and no concrete shall be placed without prior approval of the Village.
- Must meet State of Vermont Specifications.