

## REQUEST FOR PROPOSAL

**FROM: Town of Ludlow**

**ATTENTION: Brendan McNamara, Municipal Manager**

**DATE: July 25, 2024**

**The Town of Ludlow Vermont is seeking BIDS/PROPOSALS from qualified contractors for the following:**

### **PLEASANT ST. EXTENSION DRAIN REPLACEMENT PROJECT**

*(Please see attached Construction Specifications)*

**Sealed bids marked “Pleasant Street Extension Storm Drain Replacement Project” are due in the Municipal Office no later than August 28, 2024 by 10:00 am.** The bids will be opened publicly at 10:00 am in the Town Hall Conference Room and will be awarded at the Ludlow Trustees Meeting scheduled on September 3, 2024 at 6:00 pm. **Work needs to begin within fifteen (15) days of the award date.**

The Town of Ludlow reserves the right to reject any or all proposals. This solicitation in no way obligates the Village of Ludlow to award a contract.

Certificate of appropriate insurance is required with the bid proposal.

Please submit **sealed and marked** proposals to:

Town of Ludlow  
PO Box 359  
Ludlow, VT 05149  
Attn: Pleasant St. Extension Storm Drain Replacement Project

OR:

Email your bid to Brendan McNamara, Municipal Manager: [tmanager@tds.net](mailto:tmanager@tds.net)

## **Construction Specifications for Replacement of Pleasant St. Extension Road Storm Drain**

### **Description:**

Replace approximately 280' of 18" culvert to 30". Replace 1- 2' square catch basin with 4' round catch basin.

### **Pipe Ditch:**

Pipe cover shall be 2-feet with 6-inches of fine material over crown of pipe. Fine material around pipe shall be ¾ inch or less.

### **Lawn:**

Disturbed top soil shall be seeded and mulched.

### **Bituminous Paving:**

All subbase for paving shall be 18-inches of compacted crushed gravel. All road paving shall have 3-inch base and 1-inch finish.

### **Culverts:**

Change existing pipe to 30" Plastic Culvert shall be supplied by the Contractor. Installation 4-foot round catch basin to be supplied by the Contractor.

### **Debris:**

All debris shall be removed from the worksite.

### **Dig Safe:**

The contractor shall notify Dig Safe.

### **Safety:**

All job safety and trenching shall be to VOSHA standards.

### **Road Signs and Traffic Control:**

All road signs and traffic control shall be supplied by the contractor.

Contractors interested in bidding on the Pleasant St. Extension Storm Drain Replacement Project should contact Ron Tarbell at 802-770-9566.